



NOTES

1. PIPE SHALL BE FULLY SUPPORTED FOR ITS ENTIRE LENGTH BY UNDISTURBED EARTH. DIG OUT HOLLOW AT PIPE BELL.
2. TRENCH SHALL BE DRY DURING PLACEMENT
3. BACKFILL SHALL BE FREE OF UNSUITABLE MATERIAL SUCH AS LARGE ROCK, MUCK, STICKS, ROOTS & OTHER DEBRIS.
4. ALL BACKFILL SHALL BE COMPACTED TO A MINIMUM OF 95% OF AASHTO T-180 MODIFIED PROCTOR WHEN LOCATED GREATER THAN 4 FEET FROM THE EDGE OF PAVEMENT OR BACK OF CURB.
5. ALL BACKFILL SHALL BE COMPACTED TO A MINIMUM OF 98% OF AASHTO T-180 MODIFIED PROCTOR WHEN LOCATED LESS THAN 4 FEET FROM THE EDGE OF PAVEMENT OR BACK OF CURB.

TYPICAL TYPE I TRENCH DETAIL (GRANULAR SOILS)